BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE

Office Of The Executive Engineer, Dasarahalli Division

SCHEDULE-B

NAME OF THE WORK: Improvements of Roads And Foothpath in Mallasandra Ward No 13 Shettyhalli Sub Division

Sl No	Description Of Work	Unit	Qty	Rate To Be Sanctioned	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification	Cum	96.89	207.60	Rupees Two Hundred Seven And Paise Sixty Only
2	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	17.21	5505.64	Rupees Five Thousand Five Hundred Five And Paise Sixty Four Only
3	Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications.	Cum	15.08	5998.54	Rupees Five Thousand Nine Hundred Ninety Eight And Paise Fifty Four Only
4	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	85.20	4871.76	Rupees Four Thousand Eight Hundred Seventy One And Paise Seventy Six Only

Signature Of the ENGINEER for

EXECUTIVE ENGINEER
KRIDL, BBMP DIVISON
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division

9/7/19

Scanned with CamScanner

5	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	83.07	6131.04	Rupees Six Thousand One Hundred Thirty One And Paise Four Only
6	do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	142.00	150.52	Rupees One Hundred Fifty And Paise Fifty Two Only
7	Providing and fixing Pre cast solid concrete kerb stones made out of CC1:2:4 and finished with CM 1:3 plastering and finishing cutting etc - do - of size 450 x 200 x 400 mm	No's	271.11	477.00	Rupees Four Hundred Seventy Seven Only
8	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved sade after thoroughly brushing the surfae, free from mortar drops and other forign matter including preparing the surface even and sand paper smooth, cost of materials, labour, Complete as per specification.	Sqm	48.80	95.40	Rupees Ninety Five And Paise Forty Only

Signature Of The Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned with CamScanner